BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule-B"

Name of Work :- Operation and Maintenance of street light fittings in Amrutahalli ward no.08 Package Y-8 of Yelahanka Zone for the Period (10 Months).

Job Code : **P-Code: P0300**

Estimat Amount: 30.60 Lakhs **TS No:**

Sl. No	Description Of Work	Unit	Qty	Quoted Rates	In words
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **36/40 watt fluoroscent tube light street lighting systems.**	Each	42	424.54	Four Hundred Twenty Four Rupees and Fifty Four Paise
2	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day,Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **125 watt HPMV park lighting systems.**	Each	89	551.38	Five Hundred Fifty One Rupees and Thirty Eight Paise
3	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day,Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **250 watt HPSV street lighting systems.**	Each	1951	788.53	Seven Hundred Eighty Eight Rupees and Fifty Three Paise
4	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **400 watt HPSV street light/high mast lighting systems.**	Each	60	849.89	Eight Hundred Forty Nine Rupees and Eighty Nine Paise

For Anvith Infra

Proprietor

Executive Engineer
Electrical Division
Yelahanka Zone BBMP
Byataravanapura, Bangalore-92

5	Operation and Maintenance of LED street lighting system including replacement of damaged/failed /fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **24 to 45 watt LED street lighting System.**	Each	40	619.38	Six Hundred Nineteen Rupees and Thirty Eight Paise
6	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **90 watt LED street lighting systems.**	Each	771	985.05	Nine Hundred Eighty Five Rupees and Five Paise
7	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/ fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **100 to 120 watt LED street lighting systems.**	Each	20	1142.58	One Thousand One Hundred Forty Two Rupees and Fifty Eight Paise
8	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws,bolts, nuts, necessary phase separators, handle and wiring complete. Protection of Overload and Short circuit in Thermal Magnetic Release. Micro processor release shall have Earth Fault as per IS-13947. (Icu=100% lcs). In 4P MCCB , all Poles should have protection for Short-Cicrcuit/Over Load. For Microprocessor MCCBS Facility for segregating Priority and Non-Priority loads must be available in the MCCB. MCCB shall be provided with double insulation (insulation between front cover and internal power circuits to avoid any accidental contact with live current carrying path with the front cover open). Multi-pole breakers shall be designed to break all the poles simultaneously and they shall have a single mechanism.**THREE Pole 100 A 25 kA**	Each	11	6055.57	Six Thousand Fifty Five Rupees and Fifty Seven Paise
9	Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof,dust proof, water proof, corrosion proof having internally Embedded gasket on both lid and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cut-out with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility.**300 mm x 300 mm x 214 mm**	Each	11	4489.44	Four Thousand Four Hundred Eighty Nine Rupees and Forty Four Paise

I am prepared to take up the above work at rates quoted in the Schedule 'B'

For Anvith Infra

Contractor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone